

June 24, 2022

Cashman Stahler Group Attention: Greg Stahler 1910 S. Highland Ave. Lombard, IL.

Job # 30232

RE: Capron School Improvements PCO #4 - Septic Tank Removal Approximately 20'x6'x10'

Proposed Change Order to Include:

- · Pump contents of septic tank and dispose of at a sewer treatment plant
- Remove concrete walls to 24" below grade extending removal of (1) 2' wide section of wall to bottom floor of tank to prevent tank from holding water once abandoned
- Fill tank with CA7 clean aggregate

Material / disposal fees: \$ 2,033.00 + Labor and equipment: \$ 3,952.00 Increase in contract: \$ 5,985.00

Proposed septic tank removal work to be performed on a Time and Material Fee Basis with a Not-To-Exceed Fee of \$5,985.00. Provide T&M invoices to confirm final COR 04 cost.

Stenstrom Excavation and Blacktop Group:

McQuality

Kyle McQuality Project Manager / Estimator

Accepted by:

Lula

Construction Group • Excavation and Blacktop Group • Petroleum Services Group • Real Estate www.rstenstrom.com