



2606 POWER & PROCESS PIPING / PLUMBING / ENVIRONMENTAL

Capron Elementary School

09/02/2022

200 N Wooster Street
Capron Il 61012

Attention: Mr. Dean Schultz

Reference: Simplex booster pump

Dean,

Ceroni Piping Co. is pleased to submit the following quotation for your review and consideration. We propose to furnish all labor, materials, and supervision as clarified in our scope letter below.

Scope of Work:

- Mobilize materials and equipment.
- Isolate domestic water and drain system.
- Relocate existing water softener.
- Cut in a 2x1-1/4 tee to tie water softener back into the system.
- Provide pipe and material to re-pipe softener.
- Provide and install new simplex booster pump w/2" inlet and outlet.
- Provide and install bypass for booster pump.
- Insulate all new exposed piping.

Clarifications:

- Work will be done on Saturday.
- Booster pump is 230v/3ph
- Booster pump to provided 80gpm at 80psi
- 1-2-day lead time on booster pump
- Factory rep will be on site for startup.
- Piping to be propress copper
- Water will be turned off during installation of booster pump.

Not Included:

- Overtime for Sunday.
- Electrical disconnection or install of power wiring to new skid.
- Plumbing permit
- Tax

CPC labor:	\$ 3,960.00
Insulation:	\$ 1,000.00
Materials:	\$ 11,895.00
Total cost:	\$ 16,855.00

We appreciate the opportunity to work w/ you on the above referenced project. If you have any questions or concerns, please give me a call.

Sincerely,

Ceroni Piping Company

Ben Henry